Technical datasheet

Z.10h 5138 *09

23/11/2026

POWDERCOATING INSTALLATION

Deventol Powdercoating line

Brand: Deventol · Type: Powdercoating line











POWDERCOATING INSTALLATION

Complete installation	**yes**

DESCRIPTION

Complete degreasing and powdercoating installation (electrostatic) * Airmadi: degreasing unit - made in stainless steel - recuperation system - heating system - spray system - phosphatising - rinsing - with product "Parco" - passivisation - length machine: 10500 mm * Dehydratation tunnel + pre-heating oven (80°c) - separate heating system - length machine: 8000 mm * 2 powdercoating cabines - Maxon heating system (indirect) - Exhaust system - 3 hand pistols (spray units) make Sames - maximum measurement of pieces= length 2000 x height 1000 plus x width 800 mm X weight: 140 kg - length mahine: 2 cabines in total 8000 mm * Furnace - Four - Oven(220°c) - length machine: 12000 mm * Convoyer system MCM - "Power and Free"-> railsystem for transport - type: light track - Raillenght: 72 m

PRICE

Price on request

Request a quote

CONTACT

Dam-Apt BV

De Tonne 77 · 9800 Deinze · Belgium

Tel: +32 (0)9 386 15 71 · info@aptint.com

www.aptint.com · VAT BE 0405.595.996

Scan for the online datasheet