Technical datasheet

Y.06 5138 *09

23/11/2026

POWDERCOATING INSTALLATION

Deventol Powdercoating line

Brand: Deventol · Type: Powdercoating line











POWDERCOATING INSTALLATION

Loading on suspended rail (motorized)	**Yes**	Pistolspraycabin 1 with recuparation	**Yes, powderrecup**
Passage	**2000 x 1000 x 800 mm**	Handpistols	**2 powderpistols Sames**
Pistolspraycabin 2	**Yes, paintrecup**	Kiln	**Yes**

DESCRIPTION

Complete degreasing and powdercoating installation (electrostatic) * General description of the pre-treatment tunnel Airmadi 1) Entry Zone (2000mm) 2) Degreasing area - phosphating (1600mm - 120 sec.) 3) interzone with 1 ramp humidification (2000mm) 4) Rinsing zone (400mm - 30 sec.) 5) Interzone (2000mm) 6) Rinsing zone, passivation (400mm + 1 ramp cool water preference DEMINERALIZED - 30 sec) 7) Exit zone (2000mm) - length machine: 10500 mm * pre-heating oven on gas (80°c) - separate indirect heating system Maxon - length machine: 8000 mm * 2 powdercoating cabines - 1 with Cyclon powder recuperation - 1 with paint recuperation - Maxon heating system (indirect) - Exhaust system - 2 hand pistols (spray units) make Sames - maximum measurement of pieces= L 2000 x H 1000 plus x W 800

PRICE

Price on request

Request a quote

CONTACT

Dam-Apt BV

De Tonne 77 · 9800 Deinze · Belgium

Tel: +32 (0)9 386 15 71 · info@aptint.com

www.aptint.com · VAT BE 0405.595.996

Scan for the online datasheet